

PROVOST&PRITCHARD CONSULTING GROUP

455 W Fir Ave, Clovis, CA 93611 • (559) 449-2700
www.provostandpritchard.com

TECHNICAL APPLICATION ATTACHMENT T3 SCOPE OF WORK

PROVOST & PRITCHARD CONSULTING GROUP

455 W Fir Ave • Clovis, CA 93611 • (559) 449-2700
www.provostandpritchard.com

March 6, 2026

**Subject: Planning Project Scope and Fee Estimate for
Pinedale County Water District Well 5 and 10 Improvements, Fresno County, California**

PROJECT UNDERSTANDING

Pinedale County Water District (PCWD) serves water to a small community on the north side of the City of Fresno, a census designated place located in Fresno County. PCWD operates a permitted water system (Water System ID No. CA1010026) with five operating wells, Well No. 5 through Well No. 9, serving approximately 12,000 residents. Wells No. 1, 2 and 4 are inactive and Well No. 2 has been destroyed. The water system does not have any treatment other than chlorine disinfection and has recently received a compliance order from the State Water Resources Control Board (SWRCB), Division of Drinking Water (DDW) with two of their wells (Well No. 5 and Well No. 9) with the contaminant PFAS and is not meeting the State regulated maximum contaminant level. PCWD has no source of backup power at any of their active well sites. This would leave residents without water during a power outage.

PCWD is expecting to use SWRCB planning funding through the Drinking Water State Revolving Fund (DWSRF) to prepare a Financial Assistance Application for construction funding to resolve the PFAS Contamination of Wells 5 and 9. The funding application includes four packages. The scope described below is in support of the General, Financial, Technical and Environmental Packages of the application.

SCOPE OF SERVICES

The proposed scope of work is segregated into several tasks and subtasks, described below.

PHASE 001: FUNDING ADMINISTRATION

This phase of work includes preparing the monthly claims and quarterly progress reports as required by the funding agreement:

Technical Application package will be prepared as follows:

- Engineering Report (to be completed in phase ENG above)
- Problem Description
- Copies of Permits required as part of the project
- Draft Contract for professional engineering services
- Draft Plans and Specifications for both sites
- Complete attachment Checklist
- Complete TMF form for PCWD including preparing an Emergency Response Plan and Operations Plan

Environmental Package for both Sites (2 packages) will be prepared as follows:

- The Evaluation Form for Environmental Review and Federal Coordination.

DELIVERABLES

- General, Financial and Technical Package for Construction Funding Application from DWSRF

G:\Pinedale County Water District - 1674\167425002-Pinedale CWD Well 5 & 9 Planning\200 Technical\202 General\SRF Planning App\Technical\Proposal\Att T3 2026-0306 Scope of Work.docx

Engineering • Structural • Geotechnical • Surveying • Planning • Environmental • GIS • Construction Services • Hydrogeology • Consulting
Clovis • Visalia • Bakersfield • Modesto • Los Banos • Chico • Sacramento • Sonora • San Luis Obispo • Boise, ID

- Environmental Application Package, Evaluation Form for Environmental Review

PHASE 002: PREPARE ENGINEERING REPORT

This phase of work consists of preparing an engineering report that meets the requirements of the technical application package (Revision 05/2024) for the construction funding application with DWSRF. The engineering report will include the following information:

- Executive Summary and System Background including a description of the existing system and water demand analysis.
- Problem description
- Alternatives Analysis to evaluate the possible alternatives to provide reliable water supply for the PCWD community. The alternatives analysis would include design criteria, environmental impacts, land requirements, and construction and site considerations for the following alternatives, plus the “No Project” alternative, as follows:
- Consolidation Analysis to evaluate the feasibility of consolidation as an alternative solution.
- Alternative No. 1: Drill a new well (Well No. 10) to replace existing Well 9, install generator, and provide treatment for Well 5 at the existing Well 5 site.
 - This alternative would include the new Well No. 10 (to replace existing Well no. 9), hydropneumatic tank, emergency generator, destruction of existing Well no. 9 and treatment vessels for existing Well no. 5.
- Alternative No. 2: Treatment for both existing Well no. 9 and Well no. 5 at a centralized source
 - This alternative would include installing GAC vessels at a centralized site and piping each the Well no. 5 and Well no. 9 sites to the centralized property for treatment.
- Alternative No. 3: Drill a new well to replace both Well no. 5 and Well no. 9
 - This alternative would include a new well (to replace existing Well no. 9 and Well no. 5), hydropneumatic tank, emergency generator, destruction of existing Well no. 9 and Well no. 5.
- Alternative No. 4: No Project.
- Prepare estimate of probable construction cost associated with each alternative, including operations and maintenance costs.
- Prepare description of recommended alternative, including justification for recommendation, detailed cost estimate, schedule, schematic of proposed improvements, and response to climate change requirements as noted in the guidelines.
- Draft Engineering Report will be submitted to PCWD, the Division of Financial Assistance (DFA) and the Division of Drinking Water (DDW) for review and comment.
- Revise Draft Engineering Report based on comments from stakeholder agencies.
- Prepare Final Engineering Report, including a cost opinion based on the selected improvements and submit to PCWD, DFA and DDW for review and direction.

DELIVERABLES

- Draft Engineering Report in PDF format

- Final Engineering Report in PDF format

PHASE 003: HYDROGEOLOGICAL STUDY

This phase of work would include conducting a desktop hydrogeological study including a letter report on the feasibility of developing a new well that would provide potable water, sufficient capacity, including test well recommendations.

DELIVERABLES

- Hydrogeological Report in PDF format

PHASE 004: TEST WELL DESIGN

This phase of work also includes the following tasks:

- Site visit to proposed Well Site 10
- Contact regulatory agencies to confirm permit application requirements.
- Prepare construction documents for the test well construction, including specifications, 11"x17" construction drawings, and an Engineer's Opinion of Probable Construction Cost (EOPCC).
- Submit plans, specifications, and EOPCC to DDW, DFA and PCWD for review and approval.
- Make revisions to address comments and re-submit for approval.

DELIVERABLES

- Plans, Specifications, and EOPCC (Bid Package) for Test Well in PDF format

PHASE 005: TEST WELL ADVERTISEMENT

Provide bidding assistance including:

- Preparing notice to bidders and advertising in the local publication.
- Prepare electronic bid documents to be made available to bidders and maintain plan holders list.
- Coordinate and conduct one pre-bid meeting at the project site with prospective bidders.
- Review requests for information (RFIs) from prospective bidders and prepare and distribute addendum to plan holders, if necessary (up to two addenda anticipated).
- Conduct bid opening at the Pinedale CWD office, review and evaluate bid proposals, prepare a bid canvass, and make a recommendation for award of the contract.

DELIVERABLES

- Test well bid canvass and award recommendation

PHASE 006: TEST WELL CONSTRUCTION (SCOPE OUTSIDE ENGINEERING CONTRACT)

- Construction of the test well including drilling of the well and zone sampling (to be conducted outside of engineering contract).

PHASE 007: TEST WELL CONSTRUCTION ADMINISTRATION

Provide construction administration support including:

- Prepare Notice of Award and Notice to Proceed for issuance by PCWD.
- Coordinate and conduct pre-construction conference.
- Observe and oversee drilling of the test hole, and review cuttings and e-log to finalize the depth-specific zones to be sampled. Test hole depth is anticipated to be approximately 500-feet, and it is anticipated that up to eight depth-specific zones will be sampled.
 - Number of zones to be sampled will be determined during construction after the cuttings and e-log have been reviewed.
- Coordinate and perform depth-specific zone sampling.
 - Laboratory testing costs are included and account for approximately \$30,000 of the phase budget for 9 samples (8 zone samples and one source water sample).
- Test hole construction and zone sampling is anticipated to take approximately 60 days to complete.
 - It is anticipated that water quality testing and reporting by a laboratory will take approximately 30 to 45 days per sample. Turnaround times from the lab are outside of Provost & Pritchard's control and may impact the schedule.
- Review and approve monthly progress payment requests (up to two pay requests are anticipated).
- Prepare summary of water quality data and recommendations after test hole construction and sampling results are received, for submittal to PCWD, DDW and DFA.
- The engineer of record will make periodic site visits while construction is active to observe the progress of work. A total of 2 site visits are included in this scope.

DELIVERABLES

- Zone sampling and water quality analysis summary report, including a recommendation for the final design of a production well if appropriate.

PHASE 008: TOPOGRAPHIC SURVEY

This phase of work includes completing a topographic survey for PCWD parcels APN 407-410-23 and APN 405-340-22, along with PCWD temporary construction easement & PCWD access easement areas for APN 405-340-23 as follows:

- Temporary construction easement legal description and exhibit for property APN 405-340-23.
- Background research to determine property and right-of-way line locations.
- Conduct ground surveys to locate record street monuments and property corners sufficient to resolve rights of way along the project corridor.
- Conduct ground surveys to locate improvements within the project area, including visible evidence of underground utilities and visible above ground improvements.
- Prepare basemap in AutoCAD Civil3D with boundary, right of way (ROW), and topographic feature.

DELIVERABLES

- Survey base map for design in CAD format

PHASE 009: 30% PRELIMINARY CONSTRUCTION DOCUMENTS

This phase of work includes preparing the construction documents for the selected alternative to a 30% conceptual, schematic design level. This scope assumes the selected alternative will be a new well to replace existing Well no. 9 and Wellhead Treatment for Well No.5. If a new well is deemed infeasible, this scope and budget will be adjusted accordingly. The following design elements are assumed to be part of the selected project:

- New Well no. 10 on the new Well No. 10 site
- Treatment System for the existing Well No. 5 Site
- Backup power generator for Well No. 10
- Chlorine enclosure for Well No. 10
- Well Site Abandonment for Existing Well no. 9
- The following tasks are included with the 30% Construction Documents:
 - Conduct research and gather background information. Conduct project site visit and document changed site conditions from earlier site visit
 - Research existing utilities within project limits and contact utility companies to obtain record information
 - Basis of design report
 - General Project Management including coordination, billings and workload.
 - Coordination with Pinedale CWD to include system requirements, and up to two (2) virtual meetings to discuss the plans.
 - 30% level plans, specification table of contents, and engineer's opinion of probable construction cost (PS&E)
 - Submittal of plans to all stakeholders including DDW, DFA and PCWD. One (1) meeting with all stakeholders to discuss comments.

DELIVERABLES

- Electronic copy of Basis of Design report, 30% Plans, Specifications TOC and EOPCC

PHASE 010: ENVIRONMENTAL DOCUMENTS

Engineer shall prepare Environmental Documents (Phase ENV) as follows:

TEST WELL AND NEW WELL NO. 10

- Prepare a Notice of Exemption (NOE) for the test well work. Technical studies for biological and cultural resources will be required for the test well and new well on the same site.

CULTURAL STUDY

Provost & Pritchard would team with ECORP Affiliates to complete a Phase I Cultural Resources Survey/Cultural Report. This would include:

- ECORP would obtain a records search from the Southern San Joaquin Valley Information Center (IC), California State University, Bakersfield. A records search of the Native American Heritage Commission (NAHC) Sacred Lands files would also be requested.
- Fieldwork would consist of an intensive field survey of the Well no. 10 site, totaling approximately 2-acres by a qualified archaeologist.
- ECORP would prepare a written technical report that would summarize the background to the project site, records searches and tribal outreach, the field methods employed, and the results of the work described above, including recommendations for CEQA and Section 106 compliance.

BIOLOGICAL EVALUATION

- Review relevant background information.
- Perform a reconnaissance-level field survey of the Well no. 10 Project area.
- Prepare a Biological Evaluation Report that would evaluate potential project-related impacts to state and federally listed or special status species, habitats, and other sensitive biological resources. The report would be consistent with CEQA and NEPA standards.
- Prepare Initial Study/Mitigated Negative Declaration (IS/MND) in compliance with CEQA for the Well No. 10 Project. Biological and cultural technical studies will be done to a National Environmental Policy Act (NEPA) level to support any crosscutting requirements of the Water Board and are included above. Pinedale CWD would be the CEQA Lead Agency.

EXISTING WELL NO. 5

- Prepare a Notice of Exemption (NOE) for the new Treatment Vessels at the existing Well no. 5 site.

In addition to the Water Board crosscutting package requirements, the following technical studies will also be completed:

CULTURAL STUDY

Provost & Pritchard would team with ECORP Affiliates to complete a Phase I Cultural Resources Survey/Cultural Report. This would include:

- ECORP would obtain a records search from the Southern San Joaquin Valley Information Center (IC), California State University, Bakersfield. A records search of the Native American Heritage Commission (NAHC) Sacred Lands files would also be requested.
- Fieldwork would consist of an intensive field survey of the Well no. 5 site, totaling approximately 2-acres by a qualified archaeologist.
- ECORP would prepare a written technical report that would summarize the background to the project site, records searches and tribal outreach, the field methods employed, and the results of the work described above, including recommendations for CEQA and Section 106 compliance.

BIOLOGICAL EVALUATION

- Review relevant background information.
- Perform a reconnaissance-level field survey of the Well no. 5 Project area.

- Prepare a Biological Evaluation Report that would evaluate potential project-related impacts to state and federally listed or special status species, habitats, and other sensitive biological resources. The report would be consistent with CEQA and NEPA standards.

Upon receipt of one (1) set of consolidated PCWD and DFA review comments, Provost & Pritchard would finalize the documents based upon the comments received and would provide electronic copies of each document to PCWD. Provost & Pritchard would publish the NOI and distribute the NOC and the Draft IS/MND to the State Clearinghouse (SCH) and other interested agencies and individuals identified by the District for the public review period. Provost & Pritchard would prepare a draft NOD for review and comment by PCWD staff. Provost & Pritchard would file the NOD within five working days of the agency's decision to approve.

DELIVERABLES

- One (1) electronic copy of the Notice of Exemption for Test Well.
- Biological Evaluation to a NEPA level. (Test well/Well no. 10 site)
- Cultural Report to a NEPA level. (Test well/Well no. 10 site)
- One (1) electronic copy of the Administrative Draft IS/MND for new Well no. 10
- One (1) electronic copy of the Public Review Draft IS/MND for new Well no. 10
- One (1) electronic copy of the NOI, NOC, NOD for new Well no. 10
- Water Board form and crosscutters package for test well/new Well no. 10
- One (1) electronic copy of the Notice of Exemption for Well no. 5
- Biological Evaluation to a NEPA level. (Well no. 5 site)
- Cultural Report to a NEPA level. (Well no. 5 site)
- Water Board form and crosscutters package for Well no. 5 treatment site.

PHASE 011: 60% CONSTRUCTION DOCUMENTS

This phase of work includes preparing the construction documents for the selected alternative to a 60% level. This scope assumes the selected alternative will be drilling a new well (Well no. 10) to replace Well no. 9 and add treatment facilities to Well no. 5. If this alternative deems unfeasible, this scope and budget will be adjusted accordingly. The following tasks are included with the 60% Construction Documents:

- Attend one (1) meeting with PCWD to review comments.
- Coordinate with approval agencies including PCWD, DFA and DDW regarding construction document and permit requirements.
- General Project Management including coordination, billings and workload.
- 60% PS&E for Well 10, it is assumed the Plans will include approximately three (3) general sheets, two (2) plan/profile sheets, well site plan, grading plan, piping plan, well discharge piping detail sheet, and ten (10) detail sheets.
- 60% PS&E for Well 5, it is assumed the Plans will include approximately three (5) general sheets, one (1) plan/profile sheets, treatment site plan, grading plan, piping plan, treatment system detail sheet, and ten (10) detail sheets.
- Geotechnical investigation including two (2) borings to a depth of 15 to 20 feet below ground surface at each well site (4 total) and prepare a report of findings.
- 60% Electrical and Controls design for Well no. 10:

- Design for a new well power distribution system with an automatic transfer switch and backup generator, a control system panel, and provisions for onsite lighting and convenience receptacles.
- The new power and controls equipment will be located on a new concrete housekeeping pad and protected by a shade structure and a masonry block wall.
- The control system will have hand, off, and auto operational modes, with no remote-control provisions.
- Power and control provisions will be made for an onsite chlorine pump and analyzer.
- Valves onsite will be manually operated and will not require actuation.
- A prepackaged cellular communication unit would be utilized to transmit data from the site to notify the District system failures.
- Electrical Plans are projected to consist of appx. 10 sheets.
- Electrical and Control specifications
- 60% Electrical and Controls design for Well no. 5:
 - Modification of the Existing Electrical system to update to include GAC vessels, and update to the existing control system panel.
 - The new power and controls equipment will be located on a new concrete housekeeping pad/ the existing concrete pad depending on what is required.
 - Electrical Plans are projected to consist of appx. 5 sheets.
 - Electrical and Control specifications
- Submittal of plans to all stakeholders including DDW, DFA and PCWD.

DELIVERABLES

- Electronic copy of Basis of Design report, 60% Plans, Specifications and EOPCC

PHASE 012: 90% CONSTRUCTION DOCUMENTS

This phase of work includes preparing the construction documents for the selected alternative to a 90% level, sufficient for the financial assistance application for construction funding. This scope assumes the selected alternative will be drilling a new well (Well no. 10) to replace Well no. 9 and add treatment facilities to Well no. 5. If this alternative deems unfeasible, this scope and budget will be adjusted accordingly. The following tasks are included within the 90% Design subtask:

- Attend one (1) meeting with PCWD to review comments.
- Coordinate with approval agencies including PCWD, DFA and DDW regarding construction document and permit requirements.
- General Project Management including coordination, billings and workload.
- One (1) meeting, with PCWD, DDW, and DFA is anticipated. It is assumed the meeting will be conducted via telephone or video conferencing.
- Submittal of plans to all stakeholders.
- Attend one (1) meeting, each, with stakeholders to review comments.

- Revise draft documents to address comments and resubmit documents.

DELIVERABLES

- Electronic copy of Basis of Design report, 90% Plans, Specifications and EOPCC

PHASE 013: CONSTRUCTION FUNDING APPLICATION ASSISTANCE

This phase of work includes preparing the General, Financial, Environmental and Technical Application package.

Technical Application package will be prepared as follows:

- Engineering Report (to be completed in phase ENG above)
- Problem Description
- Copies of Permits required as part of the project
- Draft Contract for professional engineering services
- Draft Plans and Specifications for both sites
- Complete attachment Checklist
- Complete TMF form for PCWD including preparing an Emergency Response Plan and Operations Plan

Environmental Package for both Sites (2 packages) will be prepared as follows:

- The Evaluation Form for Environmental Review and Federal Coordination.

DELIVERABLES

- General, Financial and Technical Package for Construction Funding Application from DWSRF
- Environmental Application Package, Evaluation Form for Environmental Review

PROFESSIONAL BUDGET

This budget estimate assumes work will be performed in 2026.

PROPOSED FEE-WELL 5 AND 10 IMPROVEMENTS		
PHASE	ESTIMATED ENGINEERING FEE	ESTIMATED CONSTRUCTION FEE
Phase 001-Funding Administration	\$47,000	-
Phase 002-Prepare Engineering Report	\$85,000	-
Phase 003-Hydrogeological Study	\$17,000	-
Phase 004-Test Well Design	\$32,000	-
Phase 005-Test Well Advertisement	\$19,000	-
Phase 006-Test Well Construction	-	\$500,000
Phase 007-Test Well Construction Administration	\$113,000	-
Phase 008-Topographic Survey	\$30,000	-
Phase 009-30% Preliminary Construction Documents	\$125,000	-
Phase 010-Environmental Documents	\$112,000	-
Phase 011-60% Construction Documents	\$250,000	-
Phase 012-90% Construction Documents	\$150,000	-
Phase 013-Construction Funding Application Assistance	\$61,000	-
Subtotal Engineering and Construction Fees:	\$1,041,000	\$500,000
Total Estimated Fee:	\$1,541,000	

SCHEDULE

PROPOSED SCHEDULE-WELL 5 AND 10 IMPROVEMENTS		
PHASE	DELIVERABLE	ESTIMATED TIME FRAME
Phase 001-Funding Administration	Claims and Progress Reports	Project Duration (approximately 112 weeks)
Phase 002-Prepare Engineering Report	Draft and Final Engineering Report	40 weeks
Phase 003-Hydrogeological Study	Hydrogeology Report	4 weeks
Phase 004-Test Well Design	Test Well Design	4 weeks
Phase 005-Test Well Advertisement	Test Well Advertisement	8 weeks
Phase 006-Test Well Construction	Test Well Construction	8 weeks
Phase 007-Test Well Construction Administration	Test Well Construction Administration	16 weeks
Phase 008-Topographic Survey	CAD Basemap	4 weeks
Phase 009-30% Preliminary Construction Documents	30% PS&E	20 weeks
Phase 010-Environmental Documents	Draft IS/MND	30 weeks
	IS/MND	8 weeks
Phase 011-60% Construction Documents	60% PS&E	20 weeks
Phase 012-90% Construction Documents	90% PS&E	12 weeks
Phase 013-Construction Funding Application Assistance	Environmental Package	8 weeks
	Technical Package	8 weeks
	General Package	8 weeks
	Financial Package	8 weeks

- Agency review and laboratory turnaround time is beyond our control. If an additional submittal is required after initial review, we will be prepared to re-submit within the time frame noted above for each task after we receive agency comments.
- In addition, we have attached a preliminary Gantt Chart outlining the proposed project schedule based on the timelines noted above. Some phases will be completed concurrently, and the Gantt Chart illustrates this for your reference.

ASSUMPTIONS

- If the selected alternative is different than the assumed preferred alternative, all phase scopes and fees may need to be revised.
- If the scope of services requires Consultant to estimate quantities, areas and/or volumes for construction, such estimates are made on the basis of Consultant's experience and qualifications and represent Consultant's best judgment as a professional generally familiar with the industry and will be performed pursuant to generally accepted standards of professional practice in effect at the time of performance. However, such estimates are only estimates and shall not constitute representations, warranties or guarantees of the quantities of the subject of the estimate. If the scope of services requires Consultant to provide its opinion of probable construction costs, such opinion is to be made on the basis of Consultant's experience and qualifications and represents

Consultant's best judgment as to the probable construction costs. However, since Consultant has no control over costs or the price of labor, equipment or materials, or over the contractor's method of pricing, such opinions of probable construction costs do not constitute representations, warranties or guarantees of the accuracy of such opinions, as compared to bid or actual costs.

- If the work as described in this scope does not start in 2026, a revised fee may be necessary.
- The draft Preliminary Engineering Report cannot be completed until the results of the Test Well are obtained.
- Items to be provided by the Client: water use data or well water pumped data, system operating parameters, financial and managerial information, deeds, and condition of title (hyperlinked).
- For design, it is assumed that the PCWD water distribution system is in sufficient working condition and the distribution lines will not need to be replaced.
- PCWD will provide access to all sites.
- City of Fresno Permitting will be conducted after construction funding is obtained and is not included in this scope of services.
- Preparation of a utility service application, to bring utility power to the site will be prepared utilizing construction funding and is not included in this scope of services.
- An Initial Study/Mitigated Negative Declaration (IS/MND) is appropriate level of California Environmental Quality Act (CEQA) documentation for the proposed Project as well as completion of the SWRCB, Financial Assistance Environmental Application Package including the Evaluation Form for Environmental Review and Federal Coordination, Section IV of the form (federal crosscutters) will not be required, and this section will be left blank.
- Administrative and Screen Check reviews by PCWD, DFA and DDW will be completed in a single round of review and accompanied by a single set of consolidated comments in Word Track Changes format.
- This scope does not include focused surveys, handling of special status species, or documentation beyond what has been described in this scope of work.
- All improvements will be constructed within the City ROW or PCWD-owned property. Land acquisition is not necessary.
- Survey monuments to establish right-of-way lines will exist and be easily located.
- It is assumed that existing record information is generally accurate and that no significant discrepancies will be discovered. If the field survey discloses a material discrepancy with recorded data or if boundary points or lines to be established are not shown on any recorded subdivision map, official map, or record of survey, preparation and filing of a Record of Survey will be required in accordance with California Business & Professions Code § 8762. A separate fee proposal will be provided for Record of Survey services.
- No traffic control will be required for topographic surveys in the City or County ROW.
- No historic structures or buildings will need to be evaluated, and the services of an architectural historian will not be required.
- No Native American consultation in regard to AB 52 will be conducted.
- No archaeological site determinations of eligibility will be necessary.

- Intensive or protocol surveys for special status or endangered plant and animal species are not proposed at this time.
- This scope and fee includes the filing of the Notice of Determination with the Fresno County Clerk's Office and the payment of the Fresno County Clerk filing fee of \$50.00 and the payment of the California Department of Fish and Wildlife 2026 Environmental Document Filing Fee of \$3,043.75. <https://wildlife.ca.gov/Conservation/Environmental-Review/CEQA/Fees> It is our understanding that Provost & Pritchard will file the environmental documents.
- It is not anticipated public comments will be received; therefore, this scope and fee does not include responding to any public comments received during the public review period. If comments are received a revised Amendment will be prepared.
- The deliverables discussed above are to be provided in support of a Construction Financial Assistance Application through the SWRCB DWSRF program.
- The final, signed construction documents, suitable for bidding purposes, will be prepared utilizing construction funding, when received from the SWRCB, and is not included in this scope of services.
- PCWD staff will locate and mark existing water system facilities in the field (including water mains, valves, and services) in advance of topographic survey.
- Payment of fees for permits or agency review is not included in this scope of services or fee estimate, unless specifically noted above.
- Project will be constructed at-grade, additional pads to elevate equipment out of potential floodplain are not included in scope of work.
- Site visit will entail visual assessment of the system, no testing will occur as part of this scope of work. Client will allow for electrical enclosures to be open to expose conductors, conduit, gear, terminations, and bussing for visual evaluation.
- SCADA/Communication provisions are not included in scope of work, local control provisions will be made.
- No provisions will be made to include noise reducing enclosures in design due to the location of the new well site.
- Power quality will not be evaluated as part of this scope of work.
- Title 24 Energy calculations will not be prepared as part of this project.
- Utility fees are not included in this scope.
- Cost estimates on utility service adjustments, additions, or replacements, or recommendations for rate schedules will not be prepared as part of this scope of work and will be provided by the Utility directly.

Pinedale County Water District - Well 5 and 10 Improvements																															
Phase No.	Phase Name	Deliverable	Timeline (weeks)	Month #																											
				1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28
1	Funding Administration	Funding Administration	112																												
2	Prepare Engineering Report	Draft Engineering Report	24																												
		Agency Review Time	4																												
		Wait for Test Well Results	8																												
		Final Engineering Report	4																												
		Agency Review Time	4																												
3	Hydrogeological Study	Hydrogeology Report	4																												
4	Test Well Design	Test Well Design	4																												
		Agency Review Time	4																												
5	Test Well Advertisement	Test Well Advertisement	8																												
6	Test Well Construction	Test Well Construction	8																												
7	Test Well Construction Administration	Test Well Construction Administration/Determine if the project continues - depending on Test Well results	16																												
8	Topographic Survey	CAD Basemap	4																												
9	30% Preliminary Construction Documents	30% PS&E	20																												
		Agency Review Time	4																												
10	Environmental Documents	Draft IS/MND	30																												
		Revised IS/MND	8																												
11	60% Construction Documents	60% PS&E	20																												
		Agency Review Time	4																												
12	90% Construction Documents	90% PS&E	12																												
13	Construction Funding Application Assistance	Environmental Package	8																												
		Technical Package	8																												
		General Package	8																												
		Financial Package	8																												